

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSIONFEB 2 1966
2-2-66
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Brooks Hall

Complete Address: 1704 Liberty Bank Bldg., Oklahoma City, Oklahoma

Lease Name Shaft Well No. # 1

Location Approx. NW NE SW Sec. 18 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4754'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Aspen Drilling Company

Address: Box 783, Great Bend, Kansas License No.

Operation Completed: Hour 6:30PM Day 30th Month Jan. Year 1966

The Above well was plugged as follows:

912' of 8 5/8" surface pipe, cemented with 865 sacks. Hole was filled
with drilling mud to 300', 1st cementing plug, bridged solid with dry
cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/2/66INV. NO. 2644-4Signed: Archie Elving
Well Plugging Supervisor