

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. CW/2 SW NW

LOCATION ~~NE NW NW~~

SEC. 16 TWP. 31 RGE. 14W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well x

I have today completed supervision of plugging of:

Well No. ~~1~~ 135 Lease Skinner

Operator Great Bend Pipe & Supply Address Great Bend,

Field \_\_\_\_\_ County Barber

Total Depth ~~4375~~ 4382 Feet.

(Describe briefly the manner in which the well was plugged)

<sup>13"</sup>~~10"~~ at <sup>135</sup>~~121~~' circulated with cement - <sup>8"</sup>~~10"~~ at <sup>856</sup>~~766~~' circulated

with cement - <sup>5 1/2"</sup> at 4348' with 150 sax cement behind.

Chat to 4340' set 5 sax cement with dump bailer, pulled

<sup>3390'</sup> <sup>5 1/2"</sup>, mudded hole to 250', set rock bridge and 20

sax cement, filled with mud to 30', set rock and 10 sax

cement to bottom cellar.

**PLUGGING**  
FILE SEC. 16 TWP. 31 RGE. 14W  
BOOK PAGE 81 LINE 14

*[Signature]*  
District Conservation Agent  
RECEIVED  
Date 5-8 STATE CORPORATION COMMISSION

MAY 10 1951  
5-10-51  
CONSERVATION DIVISION  
Wichita, Kansas

*[Handwritten mark]*