

18

DISTRICT CONSERVATION AGENT'S REPORT

CP3

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 119-12

LOCATION NW-SE-SW

SEC. 29 TWP. 31 RGE. 14-W

Dry Hole _____ Abandoned Oil Well ^{gas} X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease H.W. Skinner

Operator Deep Rock Oil Corp. Address Box 429 Hutchinson-Kans.

Field _____ County Barber

Total Depth 4527 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/4 - 282 ft. Circulated with cement
7" casing set at 4480 ft. cemented with 100 sacks cement.
50 sacks of cement Pumped on bottom of hole by
Halliburton-Filling hole to 4380 ft with cement. Shot off
& Pulled the 7" casing. Mud to 282 ft. Set Rock Bridges &
20 sacks of cement at 282 ft. Mud to 30 ft. Bridge, &
10 sacks of cement at the surface.

Bill Morgan - Plugging - RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1950
10-23-50
CONSERVATION DIVISION
Wichita, Kansas

C. W. Stough -
District Conservation Agent

Date 10-18-50

PLUGGING
FILE SEC. 29 TWP. 31 R. 14W
BOOK PAGE 119 LINE 12