

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials 'CP3' and a large stylized signature or mark.

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW-NW-NE

SEC. 23 TWP. 19 RGE. 16-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mausolf Mausolf

Operator Ben F. Brack Oil Co. Inc. Address 310 Beacon Bldg. Wichita-Kans.

Field _____ County Rush

Total Depth 3760 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 792 ft. Circulated with cement.
5 1/2" casing set at 3725 ft. Cemented with 100 sacks cement.
Plugged back to 3675 ft with Baker Plug & chat.
Dumped 5 sacks of cement at 3625 ft - Shot off &
pulled the 5 1/2" casing - Hole filled with mud -
Halliburton Pumped in Plug & 100 sacks of
cement - filling hole from 700 ft to the surface
with cement.

STATE CORPORATION COMMISSION
MAY 5 1951

C. D. Stough
District Conservation Agent

Date 5-2-51

FILE 23-19-R-16W
BOOK 79 PAGE 27

F