

15-165-30112-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1966  
6-6-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Omega Drilling Inc.,

Complete Address: 427 Union Center, Wichita, Kansas

Lease Name Dirks Well No. 1

Location SW-NW-SE Sec. 22 Twp. 19 Rge. 16 (E) (W) X

County Rush Total Depth 3825

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. tools By Halib.

Address:      License No.     

Operation Completed: Hour 8 A Day 4 Month 6 Year 1966

The Above well was plugged as follows:

Above well D&A on May 27 th. 1966., and plugged according to regulations.

A few days later operator decided to do more testing, Dry hole plugs were drilled out, After testing it was decided to again D&A., and plug as instructed.

Gunned pits, circ. heavy mud set cementing plug at 420' and displaced 30 sax

cement thru drill pipe. heavy mud to 200' set cementing plug, and displaced

20 sax cement thru drill pipe. heavy mud to 40' set cementing plug, 1/3 sax hulls

and 10 sax cement to base of cellar. Plugged rat hole with 2 sax cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6/6/66

INV. NO. 3348-W