

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Handwritten initials 'JF3'

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 12 September, 19 58, authorized the following plugging operation:

Operator's Full Name: Petroleum Inc.

Complete Address: RR Great Bend, Kans.

Lease Name: McCracken Unit Well No. 1

Location: NW SW SW Sec. 32 Twp. 33 Rge. 12 (E) (W) X

County: Barber Total Depth: 4728

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

258' of 8 5/8" surface casing circulated with cement. Top perf.
4600' sand to 4590' and dump 5 sack cement top sand with dump bailer.
Shoot pipe and pull to 1800' and circulate heavy jell mud. Pull
pipe Heavy mud to 258' and set rock bridge. 20 sack cement from
rock bridge. Heavy mud to 35'. Set rock bridge from 35' add cement
to base of cellar.

Very truly yours,

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1958

CONSERVATION DIVISION
Wichita, Kansas