

KANSAS  
STATE CORPORATION COMMISSION

*R*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

*CPB*

File No. 123-16 County: Barber

Location: NW SW SW Sec. 32 Twp. 33 Rge. 12 (E) (W) W

Name of Field: \_\_\_\_\_ Total Depth: 4725

I have this date completed supervision of plugging of:

Lease Name: McCracken Unit Well No. 1

Operator's Full Name: Petroleum Inc.

Complete Address: R. R. #1, Great Bend, Kans.

Plugging Contractor: Morgan Casing Pulling Co.

Address: Hutchinson, Kans. License No. \_\_\_\_\_

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11 PM Day 19 Month September Year 1958

The above well was plugged as follows:

258' of 8 5/8" surface casing circulated with cement. Top perf. 4600'.

Hole was sanded above perf to 4590' and 5 sack cement dumped with dump

bailer. Pipe was shot and pulled to 1800' where it was circulated with

heavy well mud. Pipe pulled and hole filled to 258' with heavy mud. Rock

bridge set from 258' and 20 sack cement placed top bridge. Heavy mud to

35'. 10' rock bridge set from 35' with 10 sack cement to base of cellar.

Signed: *[Signature]*  
Conservation Division Agent

Reviewed: *[Signature]*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 32 T. 33 R12W  
BOOK PAGE 123 LINE 16

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1958  
9-26-58