

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Wright Well No. # 1

Location C E/2 NE SE Sec. 34 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4766'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:45AM Day 28th Month Jan. Year 1967

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cement circulated. 4765' of 4 1/2", no record
of cement. Top perferation 4704'. Bottom of the hole was sanded to 4700',
cemented with 3 sacks, through the dump bailer. 4210' of 4 1/2" long string
was recovered from the hole. Fluid level in the hole was at 245', rock
bridge from 245' to 235', and cemented with 25 sacks. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Ebling
Well Plugging Supervisor

DATE 1/30/67
INV. NO. 4683-4