

KANSAS
STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
 STATE CORPORATION COMMISSION

OCT 19 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name Bowers Drilling Co., Inc. & Aylward Drilling Company

Complete Address: 1434 Wichita Plaza, Wichita, Kansas

Lease Name Wright Well No. # 1

Location C E/2 NW Sec. 34 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Bowers Drilling Company, Inc.

Address: 1434 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 12:30PM Day 14th Month Oct. Year 1965

The Above well was plugged as follows:

314' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 300', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat and mouse holes
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/20/65

INV. NO. 2017-W

Signed: Archie Elving
 Well Plugging Supervisor