

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1976

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Atlantic Richfield Co

Complete Address Box 849 Great Bend, KS

Lease Name Bevans Well No. 1

Location NE/NE/NW Sec. 35 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 5151

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 11:00 AM Day 11 Month 8 Year 1976

The above well was plugged as follows:
363 ft 8 5/8 surface cemented with 350 sacks. 5144 ft 4 1/2 long string
cemented with 250 sacks. Top perf. 4624 ft. Sand to 4590 ft, 4 sacks
cement with bailer. Pulled 3800 ft 4 1/2. Set 10 ft rock bridge at
220 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/12/76

INV. NO. 3612-W

Signed: [Signature]
Well Plugging Supervisor