

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 827 Beacon Bldg., Wichita, Kansas

Lease Name Bevans "B" Well No. # 1

Location SW NW NE Sec. 35 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:00AM Day 26th Month Jan. Year 1965

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged
solid with hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/24/65

INV. NO. 594-W

Signed: Archie Elving
Well Plugging Supervisor