

KANSAS

*JP*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT -2 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued September 25, 1967.

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Carter Mandel

Complete Address: 904 Lubbock National Bldg., Lubbock, Texas 79401

Lease Name Long Well No. # 1

Location C NW SE Sec. 26 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4657'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 4:30PM Day 30th Month Sept. Year 1967

The Above well was plugged as follows:

319' of 8 5/8" surface pipe, cemented with 200 sacks. 4618' of 4 1/2" long  
string, cemented with 50 sacks. This is an open hole. Bottom of the hole  
was sanded to 4600', and cemented with 4 sacks, through the dump bailer,  
with cement from 4600' to 4550'. 4218' of 4 1/2" long string was recovered  
from the hole. Hole was bailed down to 300', bridge plug and rock bridge  
from 300' to 290', and cemented with 25 sacks, with cement from 290' to  
215'. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 10/2/67  
INV. NO. 6432-W