

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Atlantic Richfield Co.
3535 NW 58th St. Oklahoma City, Okla

Operator's Full Name Knight Casing Pulling Co.

Complete Address Box 405 Chase, Ks 67524

Lease Name Groendyke Unit Well No. 1

Location C W/2 W/2 NW Sec. 26 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4775

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks. License No. 436

Operation Completed: Hour 4:00PM Day 3 Month 4 Year 1970

The above well was plugged as follows:

311 ft of 10 inch surface pipe cemented with 300 sacks. 4775 ft of
4 1/2 long string cemented with 100 sacks. Top perf., 4676 ft. Sand
back to 4650 ft, 4 sacks cement with bailer. Pulled 3500 ft of 4 1/2.
Mud to 250 ft, 10 ft rock bridge, 35 sacks cement. Mud to 40 ft,
10 ft rock bridge, 15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: G. Russell B. Hurst
Well Plugging Supervisor

DATE 4/6/70
INV. NO. 1685-4