

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 86-36 Location: NW SE SW  
County: Barber Sec. 30 Twp. 33 Rge. 12 (E) (W)  
Name of Field or Pool: \_\_\_\_\_ Total Depth: 4614

I have this date completed supervision of plugging of:

Well No. 1 Lease McClough

Operator's Full Name Rupp Ferguson Oil Co.

Complete Address: Box 2, Ellinwood, Kans.

Plugging Contractor: Forbers Casing Pulling Co.

Address: Great Bend, Kans. License No. 2 49

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9A.M. Day 8 Month March Year 1958

The above well was plugged as follows:

250' 133/8' casing for surface. Top Perf. 4488' to 4498'. Well was  
killed with water and 50' of cement was pumped on top of perf. by Globe  
Cementing Co. Pipe was shot and pulled to about 1800' and heavy jell mud  
circulated. Hole was filled to 250' with heavy jell mud. Rock bridge  
from 250' to 240' with 35 sack cement on top bridge. Mud to 35', with  
rock bridge from 35' to 25'. Cement was placed from 25' to surface.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed:   
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 1958  
3-13-58

CONSTRUCTION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Reviewed:   
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 30 T. 33 R. 12 W  
BOOK PAGE 86 LINE 36