

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Sunray DX Oil CompanyComplete Address: 321 West Douglas, Wichita, KansasLease Name Roy Platt Well No. # 2Location 100' E/C NW NW NW Sec. 17 Twp. 33 Rge. 15 (E) (W)WCounty Barber Total Depth 5060Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Stickle Drilling CompanyAddress: 1100 Bitting Bldg., Wichita, Kansas License No. Operation Completed: Hour 4:30PM Day 20th Month March Year 1964

The Above well was plugged as follows:

231' of 13 3/8" surface pipe, cemented with 225 sacks. Fluid was up in
the hole. 1st cementing plug and 1/2 sack hulls was pushed to 225', and
cemented with 40 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with 1 sack
hulls, and cemented with 20 sacks to base cellar. Rat hole bridged and
cemented with 5 sacks.

This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/23/64INV. NO. 8835-WSigned: Archie Elving
Well Plugging Supervisor