

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed March 22, 1967

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. has this
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Sioux Petroleum Company

Complete Address: Drawer 270, Medicine Lodge, Kansas

Lease Name: Drum "A" Well No. # 1

Location: App. C SW SW Sec. 6 Twp. 33 Rge. 11 (E)(W) W

County Barber Total Depth 3600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

215' of 8 5/8" surface pipe, cement circulated with 210 sacks. Fill
hole with drilling mud to 200', bridge with 1/2 sack of hulls, and cem-
ent with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing
plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base
of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1967

Very truly yours,

Archie Elving
Conservation Division Agent

INVOICED

DATE

INV. NO.

CONSERVATION DIVISION
Wichita, Kansas