

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY O. WILES Commissioner
 FAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 9 1965
 4-9-65
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Company has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company

Complete Address: 1434 Wichita Plaza, Wichita, Kansas

Lease Name: Boggs "C" Well No. # 1

Location: NE SW NW Sec. 9 Twp. 33 Rge. 12(E) (W) W

County Barber Total Depth 4837' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cement circulated with 250 sacks.

Fill hole with drilling mud to 295', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent