

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 18 1965
 6-13-66
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drl. Co. has this
 date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Martin Keller

Complete Address: 1035 Kennedy Bldg., Tulsa, Okla.

Lease Name: Hagerman Well No. 1

Location: SW SW NW Sec. 29 Twp. 19 Rge. 16 (E)(W) X

County Rush Total Depth 3878 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 420 Ft.
and displace 25 sax cement thru drill pipe. Heavy mud to 250 Ft.
set cementing plug and displace 20 sax cement thru drill pipe.
Heavy mud to 40 Ft. set cementing plug, 1/3 sax hulls, and 10
sax cement to base of cellar. Plug rat hole with 2 sax cement.

Very truly yours,

Rio T. Massey
 Conservation Division Agent