

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Stevens of Omega Drilling Inc. has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Omega Drilling Inc.

Complete Address: #27 Union Center Wichita, Kansas

Lease Name: Dicks Well No. 1

Location: SW-NW-SE Sec. 22 Twp. 19 Rge. 16 (E)(W) X

County Push Total Depth 3825' Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Stevens was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug  
at 420 ft. and displace 70 sax cement thru drill pipe, heavy  
mud to 200 ft. set cementing plug and displace 20 sax cement  
thru drill pipe. Heavy mud to 40 ft. set cementing plug and  
1/2 sax hulls and 10 sax cement; cementing to base of cellar.

RECEIVED Very truly yours,  
STATE CORPORATION COMMISSION

MAY 31 1966  
5-31-66  
CONSERVATION DIVISION  
Wichita, Kansas

Leo Massey  
Conservation Division Agent