

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION

JAN 27 1965

CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Paul Lacey of Beardmore Drilling Co. has this date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 827 Beacon Bldg., Wichita, Kansas

Lease Name: Bevans "B" Well No. # 1

Location: SW NW NE Sec. 35 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4720 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

325' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 300', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent