

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 3, 1962.

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Perry Daniel of Central Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Perry Daniel guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 First National Bldg. Wichita, Kansas.

Fitzgerald #1
 Lease Name: *****#1 Well No. #1

Location: SW-SE-SW Sec. 7 Twp. 33 Rge. 11 (E) (W) X

County Barber Total Depth 4452' Oil Well X Abandoned

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Perry Daniel was instructed to plug the well as follows:

4452' of long string with 100 sacks cement. Plugged back to 4446'. Top perforation at 4399'. Sanded to 4390' & 3 sacks cement. 252' of 8 5/8" surface pipe circulated with cement. Hole filled to 200' with heavy mud, 10' rock bridge and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

Harmon Justice
 Conservation Division Agent