

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Curly Brau of E. K. Edmiston has this

date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Ks.

Lease Name: Bryant Well No. # 1

Location: NE SW SE Sec. 27 Twp. 33 Rge. 11 (E) (W) W

County Barber Total Depth 4625 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

238' of 8 5/8" surface pipe, cemented with 175 sacks. Fill
hole with drilling mud to 235', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent