

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 28 1964  
12-28-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Orr of Thunderbird Drilling Inc. has this date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Inc.

Complete Address: 712 Union Center, Wichita, Kansas

Lease Name: Lambert Well No. # 1

Location: C SW SW Sec. 26 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4760 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Orr was instructed to plug the well as follows:

275' of 8 5/8" surface pipe, cement circulated with 200 sacks.  
Fill hole with drilling mud to 260', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving