

CPD

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 3-19-70
 MAR 19 1970
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Tilco Et al

Complete Address: 200 Sutton Place, Wichita, Ks

Lease Name: Mills Well No. 1

Location: C NE/NW Sec. 29 Twp 30s Rge. 14 (E)(WN)

County: Barber Total Depth 4515 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

207 ft of 13 3/8 surface pipe cemented with 225 sacks.

Fill hole to 200 ft., 1/2 sack hulls, plug, 25 sacks cement.

Mud to 40 ft, 1/2 sack hulls, plug, 15 sacks cement. 2

sacks cement in rat hole.

Very truly yours,

L. Russell Bilsbaster
 Conservation Division Agent