

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Jones & Gebert Oil Co.

Complete Address: 205 Central Bldg., Wichita, Kansas

Lease Name: Hindman Well No. # 1

Location: C SE NE Sec. 11 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4474 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Comstock was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated, 4474' of  
4 1/2" long string, cemented with 125 sacks. Plugged back to  
4437'. Top perforation 4411'. Sand to 4400', cement with  
3 sacks. Fill hole with mud to 250', 10' rock bridge, cement  
with 20 sacks. Fill hole with mud to 40', 10' rock bridge,  
cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent