

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

*[Handwritten initials]*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 123-41

LOCATION C-SW/4

SEC. 4 TWP. 33 RGE. 12-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. \_\_\_\_\_ Lease Boggs "B"

Operator Shelly Oil Co Address Box #391 Hutchinson - Kans.

Field \_\_\_\_\_ County Barber

Total Depth 4930 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 376 ft - Circulated with cement.  
5 1/2" casing set at 4860 ft - Bottom of 5 1/2" casing plugged  
at 4850 ft with 5 sacks cement - Filled with sand & Chat to  
4760 ft - 5 sacks of cement - Chat to 3725 ft. Dumped  
5 sacks of cement - Shot & Pooled the 5 1/2" casing - Filled  
with mud to 390 ft. Set Rock Bridge & 15 sacks of cement  
at 390 ft - Mud to 30 ft - Plug & 10 sacks of cement at  
the surface

*J. Barcus & Sons -*

*Plugging*

**PLUGGING**  
WELL SEC 4 T 33 R 12W  
BOOK PAGE 123 LINE 41

C. M. Stough  
District Conservation Agent  
**RECEIVED**  
Date 12-3-49  
DEC 5 - 1949  
STATE CORPORATION  
COMMISSION  
KANSAS