

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 88-33 Location: CSE SE

County: Barber Sec. 6 Twp. 33 Rge. 12 (E) (W) X

Name of Field or Pool: \_\_\_\_\_ Total Depth: 3870

I have this date completed supervision of plugging of:

Well No. 2 Lease Alexander

Operator's Full Name Skelly Oil Co.

Complete Address: Box 391, Hutchinson, Kans.

Plugging Contractor: Ace Pipe Pulling Co.

Address: Great Bend, Kans. License No. 2

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2P?M. Day 2 Month April Year 1958

The above well was plugged as follows:

545 feet of 8 5/8" Surface casing, circulated with 300 sack cement.  
Plug back depth 3790'. Perf. 3550 to 3554. Hole was sanded to 3540  
with five sack cement pumped with dump bailer. Pipe was pulled to about  
1700' and heavy gell and weight mud circulated. Hole was filled to  
345' with heavy mud with rock bridge and 20 sack cement on top bridge.  
Heavy mud to 40' with rock bridge and 10 sack cement to base od cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed:   
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

APR 5 1958

CONSERVATION DIVISION

Reviewed:   
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

PLUGGING  
FILE SEC 6 T. 33 R. 12  
BOOK PAGE 8 LINE 33