

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CRB

File No. _____ County: Barber

Location: CSE NW Sec. 6 Twp. 33 Rge. 12 (E) (W)

Name of Field: _____ Total Depth: 3890

I have this date completed supervision of plugging of:

Lease Name: Alexander Well No. 2

Operator's Full Name: Upward Drilling Co.

Complete Address: 813 1st Nat Bank Bldg Wichita, Kans

Plugging Contractor: Upward Drilling Co.

Address: Chas. Ave. License No. 436

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5pm Day 13 Month 6 Year 1962

The above well was plugged as follows:

224' of 8 5/8" surface casing. Hole was
run to 3850 and 5 sacks cement dumped
with dump bucket. 5' pulled. Hole mudded
to 300. Set Pack Bridge to 190'. Dumped 20
sacks cement on bridge. Mudded to 40. Set
bridge to 30' and cement to base of collar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/18/62
INV. NO. 5194-W