

15-077-30172-0000

Form CP-3
Rev. 6-26-62

KANSAS

J.P.
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1967
9-6-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name Grace Freeman Well No. # 1

Location C SW SW Sec. 4 Twp. 31 Rge. 6 (E) W

County Harper Total Depth 4437'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 2:30PM Day 2nd Month September Year 1967

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cemented with 200 sacks. 4437' of 5 1/2" long
string, cemented with 150 sacks. Top perforation 4370'. Bottom of the hole
was sanded to 4350', and cemented with 5 sacks, through the dump bailer,
with cement from 4350' to 4310'. 3390' of 5 1/2" long string was recovered from
the hole. Hole was filled with mud to 220', rock bridge from 220' to 210',
and cemented with 25 sacks, with cement from 210' to 135'. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/6/67

INV. NO. 6264-W