

15-077-30111-0000

Form CP-3
Rev. 6-26-62

KS KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1966
11-23-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Thomas "F" Well No. # 1

Location App. C NW SW Sec. 4 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4394'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 11:15 PM Day 21st Month Nov. Year 1966

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/29/66
INV. NO. 4341-u