

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-8-70
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Spector Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks

Lease Name Grace Freeman Well No. 2

Location App. C S/2 NW/SE Sec. 4 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4714

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Co

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 11:00 AM Day 7 Month 12 Year 1970

The above well was plugged as follows:

244 ft of 8 5/8 surface pipe cemented with 250 sacks. 4714 ft of

4 1/2 long string cemented with 225 sacks. Top perf. 4298 ft. Sand
back to 4280 ft, 4 sacks cement with bailer. Pulled 3722 ft of 4 1/2.

Set 10 ft rock bridge at 240 ft. Fill hole with 4 yds redimix to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: V. Russell B. Eastern
Well Plugging Supervisor

DATE 12/8/70

INV. NO. 3018-W