

15-077-30079-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1966
4-8-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name Grace Freeman Well No. # 1

Location C SE SW Sec. 4 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:30PM Day 5th Month April Year 1966

The Above well was plugged as follows:

248' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged solid
with 1/2 sack of hulls, on fluid at 240', and cemented with 25 sacks of
cement. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with 1/4 sack of hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/8/66

INV. NO. 3005-4