

15-077-3082-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN -1 1966

6-1-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Lyle Bauer "B" Well No. # 1

Location C NE SW Sec. 5 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4751'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30PM Day 26th Month May Year 1966

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 215', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 215', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/1/66
INV. NO. 3319-W