

15-007-30151-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 31 1964
12-31-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Kansas

Lease Name Traffas Well No. # 1

Location C SW NE Sec. 7 Twp. 33 Rge. 10 (E) (W)

County Barber Total Depth 4730

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:00AM Day 30th Month Dec. Year 1964

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated. 4730' of 4 1/2" long string,
cemented with 125 sacks. Plug back to 4687'. Top perforation 4634'. Bott-
om of the hole was sanded to 4600', and cemented with 4 sacks. Fluid in
the hole was bailed down to 240'. Bridge plug was set on fluid at 240',
and 10' of rock bridge, and cemented with 25 sacks. Hole was filled with
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base
of the cellar.

3800' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/31/64

INV. NO. 441-u

Signed: Archie Elving
Well Plugging Supervisor