

15-007-00014-00-00

2 9

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 3, 1967.

AUG 23 1967
08-23-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Texaco, Inc.

Complete Address 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name George Carter Well No. # 1

Location SE NW Sec. 7 Twp. 33 Rge. 10 (E) (W) W

County Barber Total Depth 4750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Clarke Corporation, Inc.

Address Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 2:30 P.M. Day 22nd Month August Year 1967

The above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 175 sacks. 4700' of 4 1/2" long
string, cemented with 100 sacks. Top perforation 4657'. Bottom of the hole
was sanded to 4600', and cemented with 4 sacks, through the dump bailer,
with cement from 4600' to 4550'. Fluid in the hole was bailed down to 240',
bridge plug and rock bridge from 240' to 230', and cemented with 25 sacks,
with cement from 230' to 155'. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks, with cement from 30' to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-23-67

INV. NO. 6181-W