



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Handwritten initials UPB

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 13 September, 1958, authorized the following plugging operation:

Operator's Full Name: Beardmore Drilling Co.

Complete Address: 827 Beacon Bldg., Wichita, Kans.

Lease Name: Tucker "B" Well No. 1

Location: NE SE SW Sec. 5 Twp. 33 Rge. 10 (E) (W)W

County: Barber Total Depth: 4670

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

230' of 8 5/8" surface casing circulated with cement. Fill hole with heavy drilling mud to 230'. Place cementing plug at 220' with 20 sack cement top plug through drill pipe. Fill hole to 40' with heavy mud. Place cementing plug at 40' with cement to base of collar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED STATE CORPORATION COMMISSION 09-20-1958 SEP 20 1958

CONSERVATION DIVISION Wichita, Kansas