

15-007-20251-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
12-18-1974
DEC 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robinson Oil Co

Complete Address 340 R.H. Garvey Bldg. Wichita, KS

Lease Name Tucker Well No. 1

Location C SW/SW Sec. 5 Twp. 33 Rge. 10 (E) (W) W

County Barber Total Depth 4640

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 2:00 PM Day 16 Month 12 Year 1974

The above well was plugged as follows:

217 ft 8 5/8 surface cemented with 225 sacks. 4639 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4570 ft. Sand to 4400 ft, 4 sacks
cement with bailer. Pulled 3624 ft 4 1/2. Set 10 ft rock bridge at
420 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/18/74

INV. NO. 493-0

Signed: [Signature]
Well Plugging Supervisor