

15-007-20135-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1970
CONSERVATION DIVISION
Wichita, Kansas

10-21-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mack Oil Co.

Complete Address Box 400 Duncan, OK

Lease Name Stewart Well No. 1

Location C. SE/NE Sec. 20 Twp. 33s Rge. 10 (E) (W) W

County Barber Total Depth 5055

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 11:00 AM Day 19 Month 10 Year 1970

The above well was plugged as follows:

280 ft of 8 5/8 surface pipe cemented with 225 sacks. 4653 ft of 4 1/2
long string cemented with 125 sacks. Top perf. 4574. Sand back
to 4550 ft, 4 sacks cement with bailer. Pulled 4104 ft of 4 1/2. Set
10 ft rock bridge at 260 ft. Fill hole with 4 yds redimix to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-21-70

INV. NO. 2923-U

Signed: L. Russell B. Hunter
Well Plugging Supervisor