

15-007-20071-00-00

Form CP-3
Rev. 6-4-68

KANSAS

VP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1971

CONSERVATION DIVISION
Wichita, Kansas

11-08-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name J.R. Taylor

Complete Address 2612 Elmhurst Oklahoma City, OK

Lease Name Schooley Well No. 1

Location SW/SE Sec. 16 Twp. 33 Rge. 10 (E) (W)W

County Barber Total Depth 4537

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Oilfield Service

Address 107 W Fowler Medicine Lodge, Ks License No. 583

Operation Completed: Hour 4:00 PM Day 4 Month 11 Year 1971

The above well was plugged as follows:

318 ft 8 5/8 surface pipe cement circulated. 4536 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4504 ft to 4512 ft. Sand back
to 4494 ft., 4 sacks cement with bailer. Pulled 3990 ft 4 1/2. Set
20 ft rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *D. Russell Biberstein*
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4619-W