

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -007- 20647-00-00 (of this well)

Operator's Full Name Cities Service Co.

Complete Address 700 Sutton Pl., Wichita, Ks. 67202

Lease Name Grossich "A" Well No. 1

Location NE SE Sec. 12 Twp 33S Rge. 10 (E) (W)

County Barber Total Depth 4985

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:45 Am. Day 14 Month 9 Year 1979

The above well was plugged as follows:

301' 8 5/8" casing w/200 sax cement. 5 1/2" casing set at 4984' w/300  
sax cement. Plug back to 4828'-Preforated at 4828'-Sand back to 4725'  
Top sand w/ 5 sax mixed cement w/ dump bailer-Pull 3320' 5 1/2" casing  
Howco mixed & pumped 8 sax hulls-25 sax gel-Release plug-Mixed & pumped  
125 sax 50/50 posmix cement w/4% gel & 3% cc to top of casing. Shut  
in w/500# pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
09-19-1979  
SEP 19 1979

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 9-19-79  
INV. NO. 02/91-W