

1 050728

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,328-00-00

C S/2 N/2 SW, SEC. 4, T 33 S, R 12 W/R

1830 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Bartholow Well # 1

Operator: The Reach Group
Name & Address: 229 East William, Suite 500
Wichita, KS 67202

County Barber

Well Total Depth 4932 160.29 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10:00 am Day: 17 Month: December Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 4578' Perfs at 4480-4486' Pump through 4 1/2" casing with mud between plugs

1st plug pump 2 sx hulls and 20 sx cement to bottom

2nd plug at 460' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 pm Day: 17 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom, 2nd plug

at 480' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2633' 4 1/2" casing. Used common cement by Midwest

(If additional description is necessary, use BACK of this form.)

I (XXX / did not) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION

Signed

Richard W. Lacey
(TECHNICIAN)

DATE DEC 27 1985

DEC 27 1985

INV. NO. 11755

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84