

1041333

TO: STATE CORPORATION COMMISSION

1-08

API NUMBER 15-007-22,215-00-01  
C N/2 S/2 SEC. 6, T 33 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2640 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HOSPITAL UNIT "OWWO" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER

OPERATOR LICENSE # 31191

WELL TOTAL DEPTH 4020 130.65 FEET

OPERATOR: R&B OIL & GAS PRODUCTION CSG: SIZE 4 1/2" @ 4011' WITH 100 SX

NAME AND PO BOX 195 SURFACE CASING: SIZE 8 5/8" @ 262' WITH SX

ADDRESS ATTICA, KS 67009-0195

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SHAWNEE WELL SERVICE, INC LICENSE NUMBER 30346

ADDRESS PO BOX 333, ATTICA, KS 67009

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 08 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JEFF CAPPS

(COMPANY NAME) SHAWNEE WELL SERVICE, INC (PHONE) 316-254-7893

WERE: PREFS AT 3860-3862

1ST PLUG PUMPED DOWN 4 1/2" CASING WITH 100# HULLS AND 25 SX COMMON CEMENT. STOPPED PLUG AT 3511' AND SHUT IN WITH 1500#. SPOT PLUGS THRU 4 1/2" CASING.

2ND PLUG AT 600' WITH 50 SX CEMENT. 3RD PLUG AT 290' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 08 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT SPOT PLUGS THRU 4 1/2" CASING.

1ST PLUG PUMPED DOWN 4 1/2" CASING WITH 100# HULLS AND 25 SX COMMON CEMENT. STOPPED PLUG AT 3511' & SHUT IN WITH 1500#. 2ND PLUG AT 600' WITH 50 SX CEMENT. RECEIVED

3RD PLUG AT 290' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

STATE CORPORATION COMMISSION

JAN 15 1999

CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3072' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

1-26-99  
60572

1-8