

15-007-21835-00, 3-88
040139

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 12/21/81

C N/2 NE, SEC. 7, T 33 S, R 10 W/X

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name George Traffas Well # 1

Operator: H-30 Drilling Inc.

County Barber 152.59

Name & Address 251 North Water

Well Total Depth 4695 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 18 5/8 feet 317

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 13 Month: 7 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4695' Perfs at 4647-51'

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 18 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 13 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 18 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls and 100 sx cement.

Maximum pressure 1000 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3675' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
07-19-1988
JUL 19 1988

CONSERVATION DIVISION
Wichita Kansas

INVOICED (if desired, observe this plugging.)

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 7-26-88

INV. NO. 21654 SEP 12 1988