

To: 1 040669
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-15 API NUMBER 15-007-20,611-00-00 97R
C NW NW, SEC. 7, T. 33 S, R. 10 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30705
Operator: B-Y Operating, Inc.
Name & Address 251 N. Water, Ste. 12
Wichita, KS 67202

4620 feet from S section line
4620 feet from E section line
Lease Name Landwehr Well # 1
County Barber 152.58
Well Total Depth 4695 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 15 Month: 7 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4694' w/125 sx cement, Perfs at 4646-56, 4658-68, 4670-76'
1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, and 100 sx cement.

Plugging Proposal Received by Steve Middleton, Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 40 sx common cement w/3% cc. Stopped plug at 4300'.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 100 sx cement. Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3493' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form)

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE 7-24-92
INV. NO. 35783

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1992
CONSERVATION DIVISION
WICHITA, KANSAS