

1 010084

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,948 -00-00

NE NE NW, SEC. 7, T 33 S, R 10 W/EX
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

2970 feet from E section line

Operator: The Reach Group
Name & Address: 229 E. William, Suite 500
Wichita, KS 67202

Lease Name Carter Trust Well # 1

County Barber 166.60

Well Total Depth 4760 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 11:15 am Day: 30 Month: January Year: 19 86

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-675-8349

were: 4 1/2" at 4757' Perfs at 4624-4636' Pump through 4 1/2" with mud between plugs

1st plug pump 2 sx hulls and 20 sx cement to bottom

2nd plug at 900' with 50 sx cement & 5 sx gel

3rd plug at 280' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:40 pm Day: 30 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement, 2nd plug at 900' with 5 sx gel and 50 sx cement, 3rd plug at 280' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 3350' 4 1/2" casing. Used common cement by Midwest
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 11 1986
INV. NO. 12548
1-30

STATE CORPORATION COMMISSION

FEB 10 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed

[Signature]
(TECHNICIAN)

02-10-1986