

To: 1 040670
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-15 API NUMBER 15- 007-20,457- 00-00 93

C SE SW, SEC. 5, T. 33 S, R. 10 W/4
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30705

Lease Name Tucker Well # 1

Operator: B-Y Operating, Inc.
Name & Address 251 N. Water, Ste. 12
Wichita, KS 67202

County Barber

Well Total Depth 4595 149.33 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 235

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 15 Month: 7 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4591' w/250 sx cement, Perfs at 4571-81'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton & Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 15 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4521' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION
07-22-1992
JUL 22 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3447' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOLVED
(did not observe this plugging.)

DATE 7-24-92

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 35782