

10-21-87

API NUMBER 15- 007-20,537-00-00

C NW SW, SEC. 20, T 33 S, R 10 W

1980 feet from S section line

1980 feet from E section line

Lease Name Spicer Well # 1

County Barber 151.94

Well Total Depth 4675 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 348

To: 1 030877  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Operator: Range Oil Company, Inc.

Name &

Address 1120 KSB&T Bldg., 125 North Market  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P.O. Box 108, Geneseo, KS 67444

Company to plug at: Hour: 9 a.m. Day: 21 Month: 10 Year: 19 87

Plugging proposal received from Al Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6483

were: 4 1/2" at 4678' Perfs at 4618-30, 4601-11' Elevation 1523' GL

1st plug sand back to 4550' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 100 sx econolite.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10 a.m. Day: 21 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4550' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped 3 sx hulls and 2 sx hulls mixed in with first part of 75 sx cement,

released 8 5/8" wiper plug and pumped 25 sx cement.

Remarks: Used Econolite by B.J. Titan. Recovered 3160' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-28-87

CV. NO. 18691

RECEIVED STATE CORPORATION COMMISSION  
Observe this plugging.

OCT 26 1987 Signed Steve Durrant

10-26-1987  
CONSERVATION DIVISION  
Wichita, Kansas

(TECHNICIAN)