

To: 1 040593  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-27  
API NUMBER 15-007-21,795-00-00 2340  
C SE SW, SEC. 20, T. 33 S, R. 10 W/EK

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Operator: Range Oil Company, Inc.

Name & Address 1120 KSB&T Bldg.,

125 N. Market

Wichita, KS 67202

Lease Name Spicer Well # 2

County Barber 151.54

Well Total Depth 4663 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:45 a.m. Day: 27 Month: 11 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4662' w/100 sx cement, Perfs at 4617-23'

1st plug sand back to 4570' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and dump 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4565' and dumped 4 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 650 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3800' of 4 1/2" casing.

**INVOICED**

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 12-9-91

DEC 05 1991

INV. NO. 34042

CONSERVATION DIVISION  
Wichita, Kansas

12-05-1991

Signed Steve Middleton  
(TECHNICIAN)