

1 051823

8-2

API NUMBER 15-007-20,573-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

75' NE of SE NE SEC. 19, T 7 S, R 10 W/E

1927 feet from S section line

607 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name Stewart Well # 2

Operator: Range Oil Company, Inc.

County Barber

Name & Address 1120 KSB&T Bldg.,

Well Total Depth 4713 153.17 feet

125 N. Market

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 2 Month: 8 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

Notes: 4 1/2" at 4711' w/100 sx cement, Perfs at 4656-66'

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:10 p.m. Day: 2 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and

100 sx cement.

Maximum pressure 950 psi and shut in 450 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED KANSAS CORPORATION COMMISSION 08-08-1994

INVOICED observe this plugging.

CONSERVATION DIVISION WICHITA, KS

DATE 8-26-94

Signed Richard M. Lacer (TECHNICIAN)

WV. NO. 41035

# Petro-Log

## Radiation Guard Log

API # 15-007-20573-00-00

COMPANY SUN RANGE RESOURCES

WELL STEWART #2

FIELD \_\_\_\_\_

COUNTY BARBER

STATE KANSAS

Location

75' NE OF  
C-SE-NE

Sec. 19 Twp. 33S Rge. 10W

Other Services:

CDL

Permanent Datum: GROUND LEVEL Elev. 1556

Log Measured From K.B., 10 Ft. Above Perm. Datum

Drilling Measured From KELLY BUSHING

Elev.: K.B. 1566

D.F. 1563

G.L. 1556

Date	12/19/77				
Run No.	ONE				
Depth—Driller	4707				
Depth—Logger	4707				
Btm. Log Inter.	4706				
Top Log Inter.	SURF.				
Casing—Driller	8 5/8	@ 384	@	@	@
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	STARCH MUD				
Dens.	9.1	51			
pH	6.8	15.2 ml			
Fluid Loss					
Source of Sample	FLOWLINE				
R <sub>1</sub> @ Meas. Temp.	.3	@ 55 °F	@	@	@
R <sub>2</sub> @ Meas. Temp.	.22	@ 55 °F	@	@	@
R <sub>3</sub> @ Meas. Temp.	.25	@ 55 °F	@	@	@
Source: R <sub>1</sub> R <sub>2</sub>	MEAS				
R <sub>4</sub> @ BHT	.14	@ 117 °F	@	@	@
Time Since Circ.	2 HRS.				
Max. Rec. Temp.		117 °F	@	@	@
Equip.   Location	H-5	GB			
Recorded By	C. PEBLEY				
Witnessed By	MR. BECKER AND MR. BROOKS				

CONSERVATION DIVISION  
 Wichita, Kansas  
 RECEIVED  
 STATE CORPORATION  
 JUL 13 1994

07-13-1994