

To: 1-040594
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-27
API NUMBER 15- 007-21,806 -00-00 233
App. SW NW NE, SEC. 19, T. 33 S, R. 10 W7E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120
Operator: Range Oil Company, Inc.
Name & Address 1120 KSB&T Bldg.
125 N. Market
Wichita, KS 67202

4290 feet from S section line
2270 feet from E section line
Lease Name Stewart Well # 7
County Barber 153.72
Well Total Depth 4730 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5101
Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 27 Month: 11 Year: 19 91

Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4727' w/100 sx cement, Perfs at 4660-70'
1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and bump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 27 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of
sand bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 750 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmiz 6% gel by B.J. Services. Recovered 3650' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED
I (old, or next) observe this plugging.
DATE 12-9-91 DEC 05 1991 12-05-1991

Signed Stephen J. Pfeiffer
(TECHNICIAN)